

## LEGEND

DECIDUOUS TREE

Sully States

EVERGREEN TREE

SHRUBS & PERENNIALS

□ SITE BENCH

OQ SITE BOULDER

O LIGHTING

## LANDSCAPE NOTES

- 1. All plants are to be nursery grown stock from growers located in USDA hardiness zones 1, 2, 3 or 4.
- 2. Contractor to scarify ground planes prior to the installation of ground covers to promote root penetration.
- 3. New sod is to be bluegrass, per specifications. Lay sod 1 1/2" (from final grade) lower than adjacent paving grade or edger except in the center of a swale where drainage would be impeded. If sod alternate is not accepted, base bid seed areas to be 1" below pavement grade.
- 4. Install rock mulch in all planting beds as indicated on plans and details. Sample of mulch to be approved by landscape architect prior to installation. For all single trees and shrubs not in a planting bed, provide shredded cedar mulch ring, 30" diameter, 4" depth.
- 5. Separate turf from shrub beds with concrete mow band.
- 6. Contractor to install geotextile fabric for weed protection beneath all shrub beds.
- Soil preparation shall consist of composted amendment applied at a rate of 3 cubic yards per 1000 SF and tilled at a depth of 6"-9".
- 8. The Contractor shall be solely responsible for safety in, on or about the project site. Any damage to adjacent property or utilities, not designated for removal, relocation or replacement, shall be repaired and/or replaced by the Contractor at the Contractor's expense.
- 9. The Contractor shall be responsible for obtaining any permits or licenses required for the performance of the work as applicable to the project.
- 10. The landscape architect and/or owner make no warranty as to the correctness and/or completeness of the existing utility locations shown or not shown on the plans. The Contractor shall be responsible for field verifying the horizontal and vertical location of all existing utilities including water, sewer, storm drains, gas transmission lines, and other utilities above and below the surface that may affect the project. Should any discrepancy or conflict be discovered the Contractor shall notify the landscape architect immediately, and shall not continue construction until said conflict can be resolved in writing.
- 11. The Contractor shall notify all utility companies at least 48 hours prior to beginning construction to verify depth and location of all utilities.
- 12. Contractor shall take appropriate measures to protect both on site and adjacent property, trees and vegetation. Areas outside the limits of work as shown on the plans and shall remain undisturbed. Any items not intended for demolition shall be protected. Any damage will be repaired at Contractor's expense.
- 13. All planting beds, sod, & trees to be irrigated with an underground irrigation system. Irrigation design & installation to be completed by a design/build contractor. See specifications. Dryland seeded areas will not be permanently irrigated. Dryland play field to have temporary irrigation.

## PLANT SCHEDULE

CODE	EVERGREEN TREES	COMMON NAME	CONT
PI PU	PICEA PUNGENS	Colorado Spruce	10' B&B
PI PU	PICEA PUNGENS	Colorado Spruce	12' B&B
PI EN	PICEA ENGELMANNI	Engelmann Spruce	10' B&B
PI CO	PINUS CONTORTA	Lodgepole Pine	10' B&B
	DECIDUOUS TREES	COMMON NAME	CONT
PO TR	POPULUS TREMULOIDES	Quakign Asspen	1 1/2" B&B
PO TR	POPULUS TREMULOIDES	Quakign Asspen	2" B&B
PR VI	PRUNUS VIRGINIANA 'SHUBERT'	Shubert Chokecherry	2" B&B
	SHRUBS, PERENNIALS, & GRASSES	COMMON NAME	CONT
AC GL	ACER GLABRUM	Rocky Mountain Maple	#5 cont.
CA AC	CALAMAGROSTIS X ACUTIFLORA	Karl Foerster Feather Reed	#5 cont.
CO SE	CORNUS SERICEA 'BAILEY'	Bailey Redtwig Dogwood	#5 cont.
ER NA	ERICAMERIA NAUSEOSA SSP. NAUSEOSA VAR. NAUSEOSA	Dwarf Blue Rabbitbrush	#5 cont.
HE SE	HELICTOTRICHON SEMPERVIRENS	Blue Avena Grass	#5 cont.
PI MU	PINUS MUGO 'BIG TUNA'	Big Tuna Mugo Pine	#20 cont.
PR BE	PRUNUS BESSEYI	Western Sand Cherry	#5 cont.
PR PB	PRUNUS BESSEYI 'PAWNEE BUTTES'	Creeping Western Sand Cherry	#5 cont.
PR CI	PRUNUS CISTENA	Purple Leaf Plum	#5 cont.
PO FR	POTENTILLA FRUTICOSA	Native Potentilla	#5 cont.
PR VI	PRUNUS VIRGINIANA 'MELANOCARPA'	Native Chokecherry	#5 cont.
RH GL	RHUS GLABRA CISMONTANA	Rocky Mountain Sumac	#5 cont.
RH TR	RHUS TRILOBATA 'AUTUMN AMBER'	Creeping Three-Leaf Sumac	#5 cont.
so so	SORBARIA SORBIFOLIA	Ural False Spirea	#5 cont.
SY VU	SYRINGA VULGARIS	Common Purple Lilac	#5 cont.







Community + Landscape Architects


211 North Public Road, Suite 200 Lafayette CO 80026 303.664.5301 www.dcla.net

Dillon Amphitheater

Dillon, Colorado

SCD Project No.: 1236

U2 Design Development 10/14/16



LANDSCAPE PLAN